



**Office of the Deputy General Manager (Tech.)  
Project Implementation Unit, Rajgir  
Bihar State Road Development Corporation Limited  
(A Govt. of Bihar Undertaking)**

Office: Nagraj House, Bengali Para, Rajgir, Bihar Pin- 803116  
Cell No. 9431005694, E\_Mail ID- dgmpiurajgir@ gmail.com

**VERY SHORT NOTICE INVITING TENDER**

**Corrigendum – 3**

**(Through e-procurement mode only - [www.eproc.bihar.gov.in](http://www.eproc.bihar.gov.in))**

Tender Notice No.: -02/PIU-Rajgir/2014-15

Date: 02.02.2015

E-tender in two bid system i.e. Part-I, Technical Bid and Part-II, Financial Bid are invited from reputed Contractor having experience in Construction & Maintenance of road for Maintenance work from Km. 127+600 (Biharsharif) to Km. 154+500 (Bakhtiyarpur) between Rajauli-Bakhtiyarpur Section of N.H.-31

**Format of Financial Offer was as per percentage rate contract which has already been uploaded. This format has been revised from percentage rate contract to item rate contract, which is as per MORT&H SBD applicable for work costing above 5.00 Cr. work value.**

DGM (Tech.),  
BSRDCL, PIU, Rajgir

**BIHAR STATE ROAD DEVELOPMENT CORPORATION LIMITED**

**PROJECT IMPLEMENTATION UNIT, RAJGIR**

**Name of Work : Maintenance Work of NH-31 (Rajauli-Bakhtiyarpur Section) : BC Overlaying from Ch. 127+600 To 154+500 between Biharsharif to Bakhtiyarpur.**


1	Estimated Cost:	Rs. 7,62,52,419.00
2	Earnest Money:	Rs. 15,25,048.00
3	Cost Of BOQ	Rs. 10,000.00
4	Time of Completion	30 Days

**BILL OF QUANTITIES (Item Rate Contract)**

Sl. No.	Description	Unit	Quantity	Quoted Rate (in Rs.)	Quoted Amount (in Rs.)
1	<b>Tack Coat</b> Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom, all as per clause 503.				
	(i) for BM Work	Sqm	9800.00		
	(ii) for BC work	Sqm	157500.00		
2	<b>Bituminous Macadam</b> Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with mechanical control paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired.	Cum	514.500		
3	<b>Bituminous Concrete</b> Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects.	Cum	4961.25		
<b>Total Quoted Amount (in Rs.)</b>		<b>In Figures</b>			
		<b>In Words</b>			

**Permissible Limit**

1	Estimated Cost	:-	Rs. 7,62,52,419.00
2	Cost of Govt. Material	:-	
3	Permissible Limit	:-	10%
4	Rate quoted less than <u>10%</u> below estimated cost will be rejected	:-	
5	Name of the Contractor	:-	
6	Address of the Contractor	:-	
			DGM (Tech), PIU, BSRDCL, Rajgir

  
 2/2/15